

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-093-21804-00-00  
Spot: SWSWNW Sec/Twship/Rge: 26-25S-35W  
2310 feet from N Section Line, 330 feet from W Section Line  
Lease Name: NIGHTENGALE Well #: 1-26  
County: KEARNY Total Vertical Depth: 5290 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, LLC  
Address: 600 TRAVIS STE 1400  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1720		WITH 2 SX CMT
PROD	5.5	3147	0	WITH 250 SX CMT
SURF	8.625	1693		WITH 460 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2017 1:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: WES LOGAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE  
Date/Time Plugging Completed: 08/25/2017 12:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

**\*\*WELL WAS NEVER PERFORATED FOR PRODUCTION\*\*** 8/24/17: RAN CBL. FOUND TOP OF GOOD CMT AT 1690' WITH CMT STRINGERS TO 1500'. STONE CORRAL AND BOTTOM OF SURFACE CASING COVERED WITH CMT. SET CIBP @ 1720' WITH 2 SX CMT. PERFORATE 4 HOLES AT 810'. INJECTION RATE 2 1/2" BPM AT 30 PSI. 8/2817: CIRCULATE CMT FROM 810' TO 0' USING 175 SX CMT LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
0	0		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG


District: 01

Signed



(TECHNICIAN) ORLEO

SEP 15 2017

RECEIVED  
SEP - 7 2017  
KCC DOUGGE CITY 

Form CP-2/3