

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20915-00-00
Spot: N2S2SEW Sec/Twnshp/Rge: 17-33S-42W
3290 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BREEDING Well #: 1-22
County: MORTON Total Vertical Depth: 5402 feet

Operator License No.: 9228
Op Name: MARLIN OIL CORPORATION
Address: PO BOX 14630
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4670		WITH 2 SX CMT
CIBP		4875		
PROD	5.5	5402	2245	WITH 380 SX CMT
SURF	8.625	1364		WITH 475 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/01/2017 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: MARLIN CLARKE Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: Set CIBP at 4820', capped with cement. Load hole with mud. Cut off 5.5" casing at +/- 2000'. Place cement plugs as follows: 50 sacks at 1414', 40 sacks at 400', and 10 sacks at 40'.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 09/01/2017 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG STUCK IN HOLE. CUT TBG AT 4675'. SET CIBP @ 4670' WITH 2 SX CMT. 1ST PLUG AT 1420' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4898	4908		
4846	4854		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
SEP - 7 2017
KCC DODGE CITY

Signed

[Signature]
51A

(TECHNICIAN)

INVOICED

SEP 15 2017

Form CP-2/3