

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-20459-00-02
Spot: S2N2SWNE Sec/Twnshp/Rge: 5-29S-34W
1830 feet from N Section Line, 1980 feet from E Section Line
Lease Name: HALL K Well #: 9
County: HASKELL Total Vertical Depth: 5649 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL ROAD, SUITE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4070		WITH 2 SX CMT
COND	20	30		WITH 3 SX CMT
DVT	5.5	3128		WITH 500 SX CMT
PROD	5.5	5649	0	WITH 450 SX CMT
SURF	8.625	1849		WITH 675 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/23/2017 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RON ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4070' WITH 2 SX CMT. PLUG AT 1890' WITH 50 SX CMT. PLUG AT 690' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 08/23/2017 2:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4070' WITH 10 SX CMT. ATTEMPTED TO CUT CASING & WASN'T FREE. DISCOVERED DV TOOL IN HOLE & RAN CBL. FOUND TOC @ 10'. 1ST PLUG AT 1894' WITH 35 SX CMT. 2ND PLUG AT 700' WITH 75 SX CMT TO 0'. CHECK BACKSIDE WITH 2 SX CMT AT 300 PSI.

Perfs:

Top	Bot	Thru	Comments
5373	5376		
4538	4767		
4236	5293		
4130	4470		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

K. M. Sullivan
SA

(TECHNICIAN)

INVOICED

RECEIVED
SEP - 1 2017
KCC DODGE CITY

SEP 15 2017