

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-21560-00-00
Spot: S2SENE Sec/Twnshp/Rge: 17-30S-33W
2310 feet from N Section Line, 660 feet from E Section Line
Lease Name: EARLENE BLACK Well #: 1-817
County: HASKELL Total Vertical Depth: 5386 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL ROAD, SUITE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	4435		
CIBP	4.5	4830		
CIBP	4.5	4960		
PC		3100		
PROD	4.5	5125	1626	WITH 175 SX CMT
SURF	8.625	1768		WITH 625 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2017 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RON ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: TAG TOF WITH TBG & CIRCULATE HOLE WITH MUD. SPOT 50 SX CMT WITH 100# HULLS. WAIT & TAG 2943' OR HIGHER. CUT & PULL CASING. PLUG AT 1800' WITH 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 08/18/2017 4:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TBG STUCK IN HOLE. TOP OF TOF AT ~2993'. TAG TOF AT 2990'. CIRCULATE 56 BBLs MUD & SPOT 50 SX CMT WITH 100# HULLS IN THE LAST 25 SX CMT. WAIT ON CMT & TAGGED AT 2734'. TESTED CASING TO 500 PSI HOLDING. CUT & PULL CASING. 1ST PLUG AT 1822' WITH 80 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4986	4993		CHEROKEE
4899	4906		FORT SCOTT
4856	4857		
4629	4630		
4600	4606		KANSAS CITY A
4275	4276		
4171	4179		LANSING B2
4153	4164		LANSING B1

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES. COMPLIANCE ISSUE: DENIED TA SI 10 YRS**

Plugged through: TBG

District: 01

RECEIVED
SEP - 1 2017
KCC DODGE CITY

Signed

K. Sullivan
SA

(TECHNICIAN)

INVOICED

Form CP-2/3

SEP 15 2017