

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-067-20538-00-00
Spot: W2W2W2SE Sec/Twnshp/Rge: 14-28S-35W
1320 feet from S Section Line, 2540 feet from E Section Line
Lease Name: EUBANKS A Well #: 3
County: GRANT Total Vertical Depth: 3145 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL ROAD, SUITE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2914	0	WITH 595 SX CMT
SURF	8.625	785		WITH 595 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/24/2017 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RON ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: WELL IS SANDED IN TO 1500'. LOAD HOLE WITH MUD & PRESSURE TEST CASING. PERFORATE AT 1500' WITH 35 SX CMT. PERFORATE AT 815' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 08/24/2017 4:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TAG FILL @ 1500'. LOAD CASING WITH MUD & PRESSURE TEST WELL TO 600 PSI HOLDING. PERFORATE AT 1482' WITH 35 SX CMT. PERFORATE AT 815' WITH 280 SX CMT TO 0'.

Perfs:


Top	Bot	Thru	Comments
2604	2790		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
SEP - 1 2017
KCC DODGE CITY



JA

INVOICED
SEP 15 2017

Form CP-2/3