

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22694-01-00
Spot: NENWNWNE Sec/Twnshp/Rge: 31-33S-1E
195 feet from N Section Line, 2115 feet from E Section Line
Lease Name: MOORE Well #: 31-31-6-32H
County: SUMNER Total Vertical Depth: 4170 feet

Operator License No.: 35032
Op Name: K3 OIL & GAS OPERATING COMPANY
Address: 24900 PITKIN RD SUITE 305
THE WOODLANDS, TX 77386

String	Size	Depth (ft)	Pulled (ft)	Comments
I1	7	4507		201 SX
PROD	4.5	10594		500 SX
SURF	9.625	317		131 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2017 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOHN RIGAS Company: K3 OIL & GAS OPERATING COMP Phone: (832) 813-8496

Proposed Plugging Method: as per KCC requirements and recommendations

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2017 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

Perfs:

- 1) Ran in hole w/ wireline and set CIBP at 3700' (MD). Capped w/ 7 sks cement.
- 2) Loaded hole to MIT casing--hole staying full, ran in w/ wireline and perforated at 350'.
- 3) Tied into 7" casing and pumped 130sks 60/40/2% cement (no additives). Ciculrted cement up backside to surface (full returns). Well shut-in.

Remarks: CEMENTING COMPLETED BY GRESSEL OILFIELD SERVICES. TICKET # 44923. TMD = 10,596

Plugged through: CSG

District: 02

Signed *Dell Klock*, District SUPERVISOR
(TECHNICIAN)

INVOICED
SEP 15 2017

Form CP-2/3