

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN - 6 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. F. R. Holt of Shields Oil Producers, Inc. has this date requested permission to plug the following described well:

Mr. Robert J. Shields guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Kansas

Lease Name: Feltes Well No. 3338

Location: NE SW NE Sec. 34 Twp. 16 Rge. 12 (E)(W) W

County Barton Total Depth 3338 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bob Barnes was instructed to plug the well as follows:

8 5/8" 200' Cwc. 4 1/2" 3336'. Plug @ 3114'. Perf. 3057'.

Displaced 15 sax cement @ 3050" with Halliburton Cementing Company's

pump truck. Pulled pipe. Mudded hole to 200', set rock bridge,

displaced 5 sax cement. Let set over night, bailed hole dry & displaced

3 yds. ready-mix cement, cementing to base of cellar.

Very truly yours,

Don L. Swan
Conservation Division Agent