



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. F. R. Holt of Shields Oil Producers has this date requested permission to plug the following described well:

Mr. Robert J. Shields guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Kansas 67665

Lease Name: Feltes Well No. # 4

Location: NE NW NE Sec. 34 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3336 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bob Barnes was instructed to plug the well as follows:

8 5/8" 323' Cwc.

Sanded hole back to 3050' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mudded hole to 320', set rock bridge, & displaced 5 sax

cement. Let set over night. Bailed hole dry & displaced 5 yds, ready-

mix cement, cementing from 300' to base of cellar.

Very truly yours,

Don Leman
Conservation Division Agent