

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15.185.30176.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 17 1965

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Wichita, Kansas

11-17-1965

Dear Sir:

Mr. Marty Hayes of Alpine Oil & Royalty Co. has this date requested permission to plug the following described well:

Mr. Hayes guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Company

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name: Morrison "B" Well No. # 1

Location: NE NE NW Sec. 1 Twp. 21 Rge. 14 (E)(W) W

County Stafford Total Depth 3630' Oil Well     

Gas Well      Input Well      SWD Well      D & A       Lost Hole     

Mr. Hayes was instructed to plug the well as follows:

290' of 8 5/8" surface pipe, cement circulated with 285 sacks.  
Fill hole with drilling mud to 185', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent