

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

RECEIVED

SEP 16 2002

KCC WICHITA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-185-23165-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate sp or completion date

WELL OPERATOR: F.G. Holl Company, L.L.C.
(owner/company name)

KCC LICENSE # 5056
(operator's) *6/03*

ADDRESS: P.O. Box 780167 CITY: Wichita
STATE: Kansas ZIP CODE: 67278-0167 CONTACT PHONE: 316-684-8481
LEASE: Asher WELL#: #1-3 Section 3 Township 21s Range 14w
50' W. of W/2 Sw SPOT LOCATION/QQQQ COUNTY: Stafford
1320 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)
610 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT NA CEMENTED WITH NA SACKS _____
SURFACE CASING SIZE 8-5/8" SET AT 881' KB CEMENTED WITH 210 SACKS _____
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS _____

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1933 G.L. 1942 K.B. T.D. 3710 P.B.T.D. _____ Anhydrite Depth 853
(Stone Corral Formation)
CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Received plugging orders from Scott Alberg on 09/10/02. Plugged on 09/12/02 in the following
manner, using 145 sx 60/40 Poz, 6% Gel with heavy mud in hole and between all plugs; 1st plug
at 3637' with 40sx, 2nd plug at 850' with 50sx, 3rd plug at 250' with 30sx, 4th plug at 40' cemented to
surface. Rathole-15 sx. No mousehole. Plug down at 2:30 am on 09/12/02. Acid Services #5289.
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Gary Pugh / Gary Talbott Phone#: (316) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas
PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's) *6/03*
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well 9-12-02 plugged
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 09/12/02 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Asher #1-3

LOCATION: 50' W. of W/2 Sw Section 3 T 21s R 14w
API: 15-185-23165-0000 Stafford County, Kansas

OWNER: F.G. Holl Company, L.L.C.
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 03-Sep-02
COMPLETED: 12-Sep-02

TOTAL DEPTH: **DRILLER** 3710 FEET
LOGGER 3712 FEET

Ground Elevation: 1933
KB Elevation: 1942

LOG

0 -	3 FEET	Top Soil
3 -	21 FEET	Clay
21 -	60 FEET	Fine Sand
60 -	85 FEET	Sand and Gravel
85 -	190 FEET	Sand, Gravel and Clays
190 -	830 FEET	Redbeds
830 -	853 FEET	Anhydrite
853 -	1810 FEET	Shales and Salt
1810 -	3636 FEET	Limestone, Shale and Dolomite
3686 -	3710 FEET	Arbuckle

RECEIVED
SEP 16 2002
KCC WICHITA

CASING RECORDS

Surface Casing-8-5/8"

Spud at 2:15 pm on 09/03/02. Drilled 12-1/4" hole to 881'. Ran 21 joints of new 23# 8-5/8" surface casing, tally 870' set at 881' KB. Cemented with 210 sx A-Con; 3% CC, 1/4# Celloflake, and 125sx common; 2% Gel, 3% CC and 1/4# Celloflake. Cement did circulate.

Plug down at 4:30 am on 09/04/02 by Acid Services. Ticket #5229. Strapped bottom 3 joints, welded collars remaining 18 joints.

Plugging Data

Received plugging orders from Scott Alberg on 09/10/02. Plugged on 09/12/02 in the following manner, using 145 sx 60/40 Poz, 6% Gel with heavy mud in hole and between all plugs; 1st plug at 3637' with 40sx, 2nd plug at 850' with 50sx, 3rd plug at 250' with 30sx, 4th plug at 40' cemented to surface. Rathole-15 sx. No mousehole. Plug down at 2:30 am on 09/12/02. Acid Services #5289.

DEVIATION SURVEYS

1	degree(s) at	881	feet
1	degree(s) at	3510	feet
1	degree(s) at	3641	feet
3/4	degree(s) at	3710	feet