

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-22459-00-00
Spot: NWSWNWNW Sec/Twnshp/Rge: 8-21S-31W
777 feet from N Section Line, 124 feet from W Section Line
Lease Name: KSU-GOERING UNIT Well #: 1-8
County: FINNEY Total Vertical Depth: 4790 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 260 | | WITH 165 SX CMT |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/24/2017 1:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: SID DEUTSCHER Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 08/24/2017 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT.

Plugged through: DP

District: 01

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
AUG 25 2017
KCC DODGE CITY

INVOICED
SEP 15 2017

Form CP-2/3

KMS