

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-22610-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 11-29S-8E  
3210 feet from S Section Line, 2247 feet from E Section Line  
Lease Name: YOUNGMEYER 'A' Well #: 1-11  
County: ELK Total Vertical Depth: 3220 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	474		150 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/17/2017 12:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Revd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: DH Plugging Sat. 6/17/2017 10:30pm TD 3220': 50' plug @ TD, 50' plug @ 2200', 50' plug @ 1810', then fill 500' to surface. 25 sxs in rathole, and 20 sxs in the mouse hole.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 06/17/2017 10:30 AM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Plugged through drill. 60/40 poz mix was used to plug this well. Spotted 20 sack plug at 3200'. Pulled drill pipe up to 2200' and spotted 20 sack plug. Pulled up to 1810' and spotted 20 sack plug. Pulled up to 500' and circulated cement to surface. Pulled drill pipe and topped well off. A total of 205 sacks of cement were used to plug this well. well was cut off. 25 sacks of cement were used to plug rat hole and 20 sacks of cement were used to plug mouse hole.

Perfs:

RECEIVED  
KCC DIST # 3  
SEP 05 2017  
CHANUTE, KS

DS

Remarks:

Plugged through: DP

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED INVOICED  
SEP 15 2017