

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-30086-00-00
Spot: SW Sec/Twnshp/Rge: 15-34S-43W
1477 feet from S Section Line, 3950 feet from E Section Line
Lease Name: INTERSTATE J Well #: 2
County: MORTON Total Vertical Depth: 1250 feet

Operator License No.: 33373
Op Name: NAIRN, ROBERT
Address: 1120 MUNCY AVE
ELKHART, KS 67950

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD 7		1249	0	WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/28/2017 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: MARLIN CLARKE Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: 50 SX CMT AT 1250' & 150# HULLS. TAG CMT. BOND LOG 500'-0'. PUMP CMT TO SURFACE FROM 500'-0'.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/28/2017 3:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

PUMP 50 SX CMT & 150# HULLS AT 1250'. RAN BOND LOG FROM 550' TO 0'. BOND LOG SHOWED CMT TO SURFACE. TAGGED PLUG AT 965'. SPOTTED TBG AT 505' & PUMPED 95 SX CMT TO SURFACE. PULLED TBG OUT & TOPPED OFF 7" CASING.

Perfs:


Top	Bot	Thru	Comments
1249	1250		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

Signed _____



(TECHNICIAN)

RECEIVED
SEP - 1 2017
KCC DODGE CITY



INVOICED
SEP 15 2017

Form CP-2/3