

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-129-20536-00-00
Spot: NENENWN2 Sec/Twnshp/Rge: 28-34S-43W
2376 feet from S Section Line, 1379 feet from E Section Line
Lease Name: LENCUT Well #: 3
County: MORTON Total Vertical Depth: 1225 feet

Operator License No.: 33373
Op Name: NAIRN, ROBERT
Address: 1120 MUNCY AVE
ELKHART, KS 67950

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1211	0	WITH 400 SX CMT
SURF	8.625	402		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/25/2017 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: MARLIN CLARKE Company: SARGENT LILLARD CASING PULL Phone: (620) 544-5242

Proposed Plugging Method: PUMP 35 SX CMT WITH 150# HULLS 1225'-925'. TAG PLUG. RUN CBL FROM 520' TO 0'. FILL WITH CMT FROM 505' TO 0'. FILL ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2017 2:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

PUMP 35 SX CMT WITH 150# HULLS AT 1225'. TAGGED PLUG AT 905'. RAN CBL FROM 525' TO 0'. TOC @ 25'. PUMP 61 SX CMT FROM 505' TO 0'. TOP OFF ANNULUS WITH 4 SX CMT.

Perfs:

Top	Bot	Thru	Comments
1211	1225		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

INVOICED

SEP 15 2017

Form CP-2/3

RECEIVED
SEP - 1 2017
KCC DODGE CITY