

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-22316-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 35-30S-12E
5008 feet from S Section Line, 2317 feet from E Section Line
Lease Name: PICKETT Well #: 1
County: ELK Total Vertical Depth: 1630 feet

Operator License No.: 4448
Op Name: PERKINS OIL ENTERPRISES, INC.
Address: PO BOX 707
HOWARD, KS 67349

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| CIBP | | 1360 | | |
| PROD | 4.5 | 1630 | | 214 SX |
| SURF | 8.625 | 40 | | 25 SX |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/18/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: PERKINS OIL ENTER. Company: _____ Phone: (620) 374-2133

Proposed Plugging Method: RUN 1" TO TD PUMP GEL & THEN PUMP A 50' CEMENT PLUG PULL PIPE TO 900' PUMP 50' PLUG PULL PIPE TO 275' PUMP CEMENT TO SURFACE PULL REST OF PIPE & TOP OFF.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 07/18/2017 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1420' and hit plug. Gelled hole and spotted 5 sack plug. Pulled up to 900' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 38 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1590 | 1600 | | |
| 1257 | 1264 | | |

RECEIVED
KCC DIST # 3
AUG 31 2017
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH KCC.

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

SEP 15 2017