

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-21426-00-00
Spot: NENENE Sec/Twnshp/Rge: 9-30S-7W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: EARLY Well #: 3-9
County: KINGMAN Total Vertical Depth: 4200 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4197		150 SX
SURF	8.625	263		175 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/24/2017 8:00 AM
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Rcvd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE Phone: (620) 254-7251

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 08/24/2017 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET @ 4050' & CAPPED WITH 2 SKS CEMENT. THE CASING WAS PERFORATED AT 1100', 700' & 310'. TUBING WAS RUN TO 1100' WHERE 50 SKS CEMENT WAS SPOTTED. PULL TUBING TO 700' WHERE 50 SKS CEMENT WAS SPOTTED. PULL TUBING TO 310' & CIRCULATED CEMENT TO SURFACE WITH 125 SKS CEMENT.

Perfs:


Top	Bot	Thru	Comments
4100	4110		

Remarks: BASIC SERVICES, COMMON 3% CACL

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

INVOICED

SEP 15 2017

18