

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-30118-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 19-30S-9W  
1650 feet from S Section Line, 990 feet from E Section Line  
Lease Name: WESTERMAN C Well #: 2  
County: KINGMAN Total Vertical Depth: 4432 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 124 N MAIN PO BOX 195  
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4427		125 SX
SURF	8.625	216		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2017 8:00 AM  
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.  
Proposal Rcvd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE Phone: (620) 254-7251

Proposed Plugging Method: AS PER KCC RULES & REGS. CASING LEAK 1592'-1770'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/22/2017 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @4375' & SPOTTED 2 SX CEMENT ON BP. PERF'D CASING AT 1500', 1000, AND 270'. RAN TUBING TO 1500' & SPOTTED 50 SX CEMENT. TAGGED CEMENT AT 1120'. PULLED TUBING TO 1000', SPOTTED 50 SX CEMENT. PULLED TUBING TO 270' & CIRCULATED CEMENT TO SURFACE WITH 125 SX CEMENT.


Perfs:

Top	Bot	Thru	Comments
4406	4412		

Remarks: BASIC CEMENT, COMMON 3% CACL.

Plugged through: TBG

District: 02

Signed   
(TECHNICIAN)

INVOICED  
SEP 15 2017

JK