

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-20977-00-00
Spot: N2SESE Sec/Twnshp/Rge: 16-31S-8W
990 feet from S Section Line, 660 feet from E Section Line
Lease Name: LONG Well #: 3
County: HARPER Total Vertical Depth: 4405 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4395		100 SX
SURF	8.625	265		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/07/2017 8:00 AM
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Rcvd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE, INC. Phone: (620) 254-7251

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/07/2017 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET WIRELINE B.P. AT 4350' & CAPPED WITH 2 SKS CEMENT. PERF'D 5 1/2" CASING AT 1350', 900' & 310'. RAN TUBING TO 1350' & SPOTTED 40 SKS COMMON CEMENT. TAGGED CEMENT AT 1285'. PULL TUBING TO 900' & SPOTTED 40 SKS CEMENT. PULLED TUBING TO 310' & CIRCULATED WITH 125 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4393	4405		

Remarks: BASIC SERVICES. COMMON CEMENT 3% CACL.

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

SEP 15 2017

✓