

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22421-00-00
Spot: SENWNENW Sec/Township/Rge: 2-34S-12W
4719 feet from S Section Line, 3367 feet from E Section Line
Lease Name: FARNEY Well #: 1-2
County: BARBER Total Vertical Depth: 5059 feet

Operator License No.: 30991
Op Name: RED CEDAR OIL, LLC
Address: 3816 SE PAGEANT PO BOX 221
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3940		WITH 2 SX CMT
CIBP		4595		WITH 2 SX CMT
PROD	4.5	5055	2100	WITH 275 SX CMT
SURF	8.625	287		WITH 185 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/25/2017 2:30 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4600' WITH 2 SX CMT. CIBP @ 3970'. PLUG AT 660' WITH 12 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2017 3:30 PM KCC Agent: STEVE PFEJFER

Actual Plugging Report:

SET CIBP @ 4595' & PUT 2 SX CMT ON TOP OF CIBP. HOLE WENT ON VACUUM. SET CIBP @ 3940' (ABOVE POSSIBLE PERF INTERVAL NOT REPORTED). HOLE STAYED FULL. PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 651' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4661	4681		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed

Stephen J Pfejfer
(TECHNICIAN)

RECEIVED
AUG 28 2017
KCC DODGE CITY

INVOICED

SEP 15 2017

Form CP-2/3

KMS