

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21512-00-00
Spot: E2NESWNE Sec/Twnshp/Rge: 25-22S-5W
1650 feet from N Section Line, 1325 feet from E Section Line
Lease Name: DODGE A Well #: 2
County: RENO Total Vertical Depth: 3873 feet

Operator License No.: 30878
Op Name: RESSLER WELL SERVICE, INC.
Address: PO BOX 525
BURRTON, KS 67020

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	150		160 SX
PROD	5.5	3863	1500	200 SX
SURF	8.625	350		325 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2017 12:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: LARRY RESSLER Company: _____ Phone: (620) 664-0597

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 06/28/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

ON 6/27/17 DUMPED SAND TO PLUG BOTTOM. TAGGED AND FILLUP W/WIRELINE @ 3800'. MIXED AND BAILED 5 SKS OF CEMENT ON TOP OF SAND. SHOT 5.5 CASING OFF @ 1500 FT. PULLED CASING UP TO 800 FT. PUMPED 50 SX. PLUG OF CLASS A CEMENT WITH 3% CC. PULLED CASING OUT OF HOLE. RAN IN WITH WIRELINE AND DID NOT TAG PLUG. RIHW TUBING TO 800 FT. SPOT SECOND 50 SK. PLUG W/ 3% CC. PULLED TUBING UP TO 375 FT. WAITED 1 HOUR. RAN IN WITH WIRE LINE AND TAGGED PLUG @ 500 FT. MIXED AND PUMPED 165 SKS OF 60/40 POZ. GETTING LIMITED RETURNS. PULLED TUBING & SHUT DOWN. 06/28/2017 RAN IN WITH WIRELINE AND TAGGED HARD CEMENT @ 70 FT. TRIPPED IN TUBING, MIXED AND PUMPED 50 SKS OF COMMON CEMENT AND CIRCUALTED GOOD CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3863	3873		

Remarks: COPELAND CEMENTING PROVIDED CEMENT.

Plugged through: TBG

District: 02

Signed _____

B. J. Hope

(TECHNICIAN)

INVOICED

SEP 15 2017

Form CP-2/3

sk