

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21385-00-00
Spot: SWSE Sec/Twnshp/Rge: 16-33S-6W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: CAROTHERS BROS Well #: A 1
County: HARPER Total Vertical Depth: 4504 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4499		175 SX
SURF	8.63	264		170 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/01/2017 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES Phone: (580) 251-9618

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/06/2017 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:


SET WIRELINE B.P. AT 4392'. LOAD HOLE WITH 65 BBLs OF MUD. SPOT 2 SKS CEMENT ON B.P. THRU DUMP BAILER. RECOVERED 4 1/2" CASING FROM 1208' AND LAYED OUT. TIH WITH TUBING TO 1150' & SPOT 35 SX CEMENT. PULLED TUBING TO 650' & SPOT 35 SX CEMENT. PULLED TUBING TO 310' & CIRCULATED CEMENT TO SURFACE WITH 100 SKS CEMENT.

Remarks: ORR ENTERPRISES. CLASS C CEMENT

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

INVOICED

SEP 15 2017

Form CP-2/3

✓