

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22723-01-00
Spot: SENWNENW Sec/Twnshp/Rge: 8-32S-3W
350 feet from N Section Line, 1700 feet from W Section Line
Lease Name: FORSTER 3203 Well #: 1-8H
County: SUMNER Total Vertical Depth: 4900 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		6 SX
II	7	4900		350 SX
PROD	7	4900		350 SX
SURF	13.375	260		420 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/08/2017 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES Phone: (580) 251-9618

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/08/2017 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TIH WITH CIBP ON TUBING. RAN TUBING TO 4200' & RELEASED B.P.
CIRCULATED HOLE WITH 160 BBL MUD FOLLOWED WITH 70 SXS CEMENT. TOH
WITH TUBING. RECOVERED CASING FROM 1206' & LAYED DOWN. TIH WITH
TUBING TO 700' & SPOT 50 SX CEMENT. PULL TUBING TO 300' & CIRCULATE
CEMENT TO SURFACE WITH 40 SKS CEMENT. TOH WITH TUBING, TOP OFF
CEMENT.

Perfs:

Top	Bot	Thru	Comments
8316	8580		
7932	8240		
7619	7844		
7248	7536		
6912	7175		
6588	6830		
6256	6522		
5838	6058		
5534	5772		
5232	5473		
4936	5156		
4554	4774		

Remarks: ORR ENTERPRISES. CLASS C CEMENT. TMD = 8657

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN) VOICED

SEP 15 7⁰⁰7

Form CP-2/3

✓
SK