

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21466-00-00  
Spot: SWNWESW Sec/Twnshp/Rge: 31-33S-6W  
2000 feet from S Section Line, 1575 feet from W Section Line  
Lease Name: MCKEE Well #: 1-31  
County: HARPER Total Vertical Depth: 5060 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5060		175 SX
SURF	8.63	213		150 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2017 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-6002

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/29/2017 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TRIPPED IN HOLE WITH CIBP & SET AT 4446'. CIRCULATED CASING WITH 105 SX MUD AND 70 SX CEMENT. TRIP OUT OF HOLE WITH TUBING. RECOVER & LAY DOWN 1526' OF 5 1/2" CASING. TRIP IN HOLE WITH TUBING TO 1300' & SPOT 50 SXS CEMENT. PULL TUBING TO 900' & SPOT 50 SXS CEMENT. PULL TUBING TO 300' & CIRC 100 SKS CEMENT. LAY DOWN TUBING AND TOP OFF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4967	4971		SPF
4496	4503		SPF

Remarks: ORR ENTERPRISES. CLASS "C" CEMENT

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED  
SEP 15 2017

Form CP-2/3