

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-203-20267-00-00
Spot: SWNWSESW Sec/Twnshp/Rge: 12-19S-36W
981 feet from S Section Line, 3661 feet from E Section Line
Lease Name: AGUILERA Well #: 14-12
County: WICHITA Total Vertical Depth: 5052 feet

Operator License No.: 34319
Op Name: SDOCO, LLC
Address: PO BOX 369
LITTLETON, CO 80160

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4480		WITH 2 SX CMT
DVT		2999		WITH 225 SX CMT
PROD	5.5	5016	0	WITH 265 SX CMT
SURF	8.625	336		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2017 9:00 AM
Plug Co. License No.: 8438 Plug Co. Name: POST & MASTIN WELL SERVICE, INC.
Proposal Revd. from: MONTIE GREER Company: SDOCO Phone: (620) 355-1812

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2017 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4480' WITH 2 SX CMT. PUMP 70 SX CMT AT 3030' TO 2300'. FULL CIRCULATION. PUMP 135 SX CMT AT 1300' TO 0'. TOP OFF WITH 10 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
4966	4974		
4569	4572		
4557	4561		
4545	4548		
4532	4538		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
SA

(TECHNICIAN)

RECEIVED
SEP - 1 2017
KCC DODGE CITY

INVOICED
SEP 15 2017