

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21103-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 12-17S-33W
4868 feet from S Section Line, 351 feet from E Section Line
Lease Name: ELLIS Well #: 1-12
County: SCOTT Total Vertical Depth: 4781 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY SUITE 2
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 2 SX CMT
CIBP		4340		
DVT		2365		WITH 400 SX CMT
PROD	5.5	4493	0	WITH 620 SX CMT
SURF	8.625	338		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2017 3:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: TY LUNN Company: STELBAR OIL CORPORATION Phone: (316) 264-8378

Proposed Plugging Method: SET CIBP @ 4150' WITH 2 SX CMT. RTIH 2370' WITH CMT TO 0'. CHECK BACKSIDE WITH CMT TO 500 PSI.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2017 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4150' WITH 2 SX CMT. RUN TBG TO 2363' & CIRCULATE CMT TO SURFACE WITH 215 SX CMT. TOP OFF 5 1/2" CASING WITH 20 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
4369	4375		
4184	4190		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

RECEIVED
AUG 24 2017
KCC DODGE CITY

Signed

Kenn Jeulik
(TECHNICIAN)

INVOICED
SEP 15 2017

Form CP-2/3

KMS