

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-24088-00-00
Spot: W2NWSW Sec/Twnshp/Rge: 22-25S-5E
1980 feet from S Section Line, 330 feet from W Section Line
Lease Name: MILLS A Well #: 41
County: BUTLER Total Vertical Depth: 2468 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	263		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/28/2017 12:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: _____ Company: VESS OIL CORP Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 08/28/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

HOLE IS FULL OF MUD, WITH DRILL PIPE @ 2460' QES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL & DISPLACED IN OPEN HOLE. PULLED DRILL PIPE TO 314', QES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL & DISPLACED IN CASING. PULLED DRILL PIPE @ 60', QES MIXED & PUMPED 20 SXS TO SURFACE. CEMENT CIRCULATED. 20 SXS IN RATHOLE. TOTAL 110 SXS 60/40 POZMIX 4% GEL. TICKET #53440.

Remarks: DRY HOLE

Plugged through: DP

District: 02

Signed

Duane Krueger
(TECHNICIAN)

INVOICED

SEP 15 2017

Form CP-2/3

JK