

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-24087-00-00
Spot: SWSWNWNE Sec/Twnshp/Rge: 21-25S-5E
1000 feet from N Section Line, 2610 feet from E Section Line
Lease Name: CHESNEY A Well #: 241
County: BUTLER Total Vertical Depth: 2499 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	262		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/18/2017 8:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: _____ Company: VESS OIL CORP Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 08/18/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report: _____ Perfs: _____

HOLE FULL W/MUD. WITH DRILL PIPE @ 2391' QES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL & DISPLACED IN THE OPEN HOLE. PULLED DRILL PIPE @ 314' QES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL & DISPLACED IN CASING. PULLED DRILL PIPE AT 60', QES MIXED & PUMPED 20 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. 20 SXS IN RAT HOLE. TOTAL 110 SXS 60/40 POZMIX 4% GEL. TICKET #54657.

Remarks: DRY HOLE

Plugged through: DP

District: 02

Signed Duane Krueger
(TECHNICIAN)

INVOICED
SEP 15 2017