

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-25754-00-00
Spot: SEWNENE Sec/Twnshp/Rge: 26-29S-18E
600 feet from N Section Line, 800 feet from E Section Line
Lease Name: WHITE FARMS INC 26 Well #: 1
County: NEOSHO Total Vertical Depth: 1144 feet

Operator License No.: 5491
Op Name: W & W PRODUCTION COMPANY, GEN
Address: 1150 HWY 39
CHANUTE, KS 66720

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 1142 | | 165 SX |
| SURF | 8.625 | 23 | | 4 SX |
| T1 | 2.375 | 1075 | | |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/22/2017 12:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MICHAEL WIMSETT Company: W & W PRODUCTION Phone: (620) 431-4137

Proposed Plugging Method: Run 2" cement string to T.D. & pump cement to surface with Portland Cement.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 06/22/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2 inch cement string was run to 1142 feet. Two sacks of gel were pumped. 75 sacks of cement were then spotted. The cement string was pulled to 250 ft and the well filled to surface with an additional 45 sacks of cement. A total of 120 sacks of portland cement were used to plug well.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1034 | 1038 | | |
| 980 | 982 | | |
| 974 | 977 | | |
| 758 | 761 | | |
| 721 | 724 | | |
| 696 | 700 | | |
| 617 | 621 | | |
| 604 | 608 | | |

RECEIVED
KCC DIST # 3
SEP 11 2017
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)

INVOICED

SEP 15 2017