

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23739-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 33-34S-11W
314 feet from S Section Line, 4846 feet from E Section Line
Lease Name: KEESECKER Well #: 4
County: BARBER Total Vertical Depth: 5372 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4700		WITH 2 SX CMT
CIBP		5090		
PROD	5.5	5247	3028	WITH 225 SX CMT
SURF	10.75	211		WITH 240 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/30/2017 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DERRICK BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4700' WITH 2 SX CMT. PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 240' WITH 70 SX CMT. PLUG AT 40' WITH 40 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/30/2017 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4700' WITH 2 SX CMT. 1ST PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5103	5106		
4776	4836		
4762	4768		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed _____

RECEIVED
SEP - 1 2017
KCC DODGE CITY

SA

(TECHNICIAN)
INVOICED
SEP 1 2017