

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20775-00-00
Spot: W2W2E2SW Sec/Township/Rge: 4-22S-32W
1335 feet from S Section Line, 3862 feet from E Section Line
Lease Name: GREATHOUSE C Well #: 2-4
County: FINNEY Total Vertical Depth: 2910 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1170		
CIBP		2587		WITH 10 SX CMT
CIBP		2690		
PROD	5.5	2910	0	WITH 450 SX CMT
SURF	8.625	320		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/28/2017 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: MONTE Company: XTO Phone: (405) 319-3212

Proposed Plugging Method: CIBP @ 2594' WITH 10 SX CMT. PUMP 70 SX CMT AT 2100'-1400'. CBL FROM 1400' TO 0'.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2017 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2587' WITH 10 SX CMT. 8/29/17: PUMP 70 SX CMT WITH 150# CEDAR FIBER & 2% CC AT 2100' TO COVER ANHYDRITE & GLORIETTA CASING LEAK. CIRCULATED. TOOH WITH TBG ATTEMPT TO LOAD THE HOLE TO RUN CBL. WOULD NOT LOAD. FLUID LEVEL AT 450'. SET 2ND CIBP @ 1170'. LOAD & TEST CASING TO 300#. HOLDING. CIRCULATE HOLE WITH 30 BBLS. RUN CBL FROM 1160' TO 0'. FOUND TOC @ 50'. RUN TBG TO 1170'. 8/30/17: FILL CASING WITH 120 SX CMT. TOP OFF WITH 5 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2696	2706		
2644	2672		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
EA

(TECHNICIAN)
INVOICED

RECEIVED
SEP - 1 2017
KCC DODGE CITY

SEP 15 2017