

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-19037-00-00
Spot: NESWSWNW Sec/Twnshp/Rge: 17-19S-21W
3287 feet from S Section Line, 4637 feet from E Section Line
Lease Name: PETER STIEBEN Well #: 2
County: NESS Total Vertical Depth: 4398 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>4058</u>	PC	4.5	1059		CEMENTED TO SURFACE
Op Name: <u>AMERICAN WARRIOR, INC.</u>	PROD	4.5	4397	0	WITH 200 SX CMT
Address: <u>PO BOX 399</u> <u>GARDEN CITY, KS 67846</u>	SURF	8.625	252		WITH 200 SX CMT

Well Type: SWD UIC Docket No: D10478.0 Date/Time to Plug: 08/16/2017 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: TIE ONTO CASING & PUMP 200# HULLS & CMT TO BOTTOM.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2017 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TIED ONTO CASING & TRIED TO TAKE AN INJECTION RATE. CASING PRESSURED TO 5500# & HELD. RAN TBG TO 980' & PUMP 200# HULLS WITH 80 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
1023	1050		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

INVOICED
SEP 13 2017

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
AUG 22 2017
KCC DODGE CITY

KMS