

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-20179-00-00
Spot: SWNENENE Sec/Township/Rge: 17-17S-20W
4638 feet from S Section Line, 597 feet from E Section Line
Lease Name: ELMORE Well #: 2
County: RUSH Total Vertical Depth: 4051 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2230		WITH 2 SX CMT
CIBP		2700		WITH 2 SX CMT
CIBP		3230		WITH 2 SX CMT
DVT		1180		CMT TO 320'
PROD	5.5	4050	0	WITH 125 SX CMT
SURF	8.625	244		WITH 175 SX CMT

Well Type: SWD UIC Docket No: D14628.0 Date/Time to Plug: 08/25/2017 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP'S AT 3230', 2700' & 2230' WITH 2 SX CMT ON TOP OF EACH. RUN BOND LOG. PLUG AT 1400' WITH 30 SX CMT. 300' TO SURFACE & CHECK BACKSIDE OR PERFORATE AT 300' & CIRCULATE CMT DEPENDING ON BOND LOG RESULTS

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2017 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP'S AT 3230', 2700' & 2230' WITH 2 SX CMT ON EACH. RAN BOND LOG. SPOTTY CMT FROM 340' TO SURFACE. RAN TBG TO 1395' & SPOTTED 20 SX CMT. PULLED TBG TO 292' & CIRCULATED CMT TO SURFACE WITH 45 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 260# WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3280	3443		
2780	2810		
2745	2760		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

RECEIVED
AUG 28 2017
KCC DODGE CITY

Signed



(TECHNICIAN)

INVOICED

SEP 15 2017

KMS