

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-115-19146-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 3-19S-2E
1006 feet from S Section Line, 3911 feet from E Section Line
Lease Name: HETT Well #: 7
County: MARION Total Vertical Depth: 3140 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 200 W DOUGLAS, SUITE 101
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3110		120 SX
SURF	8.625	150		120 SX

Well Type: SWD UIC Docket No: D23037.0 Date/Time to Plug: 08/23/2017 12:45 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: TANNER NELSON Company: TREK AEC Phone: (620) 755-2571

Proposed Plugging Method: As per Kansas Corporation Commission's Rules and Regulations, as per their recommendations.

Plugging Proposal Received By: WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2017 12:00 AM KCC Agent: JERRY SPARLING

Actual Plugging Report:

Bottom plug at 3410 feet pumped 50 sx. Common cement with 3% gel and 30 lbs of cottonseed hulls. Ran 27/8 tubing into 5 1/2 to 330 feet. Ran 1" down backside to 300 feet pumped 110 sx common cement circulated to surface. Pulled tubing and 1" and topped off with 10 sx common cement.

Perfs:

Top	Bot	Thru	Comments
3380	3410	TBG	
0	300	CSG	

Remarks: QES TICKET #54710

Plugged through: CSG

District: 02

Signed Jerry Sparring
(TECHNICIAN)

INVOICED

Form CP-2/3

SEP 15 2017

✓