

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-21,984.0000

C SE SW, Sec. 3, T 21 S, R 14 (W/E)

660 feet from N/S section line

1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9282

Lease Name Asher Well # 1

Operator: General Atlantic Energy Corp.  
Name & 511 Sixteenth Street, # 500  
Address Denver, CO 80202

County Stafford

Well Total Depth 3770 feet 122.53

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Woodman & Iannitti Drilling Company License Number 5122

Address P. O. Box 308, Great Bend, KS 67503

Company to plug at: Hour: 5:00 am Day: 30 Month: April Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Richard Wheeler

(company name) Woodman & Iannitti (phone) 316-587-3447

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 810' with 50 sx cement

2nd plug at 430' with 60 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement.

6th plug to circulate mousehole with 10 sx cement  
Signed Plyde Wiley  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 am Day: 30 Month: 4 April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 810' with 50 sx cement, 2nd plug at 430' with 60

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rathole with 15 sx cement. 6th plug to circulate

mousehole with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun # 19232

RECEIVED  
STATE CORPORATION COMMISSION

MAY 03 1984

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

INVOICED

DATE 5-4-84

INV. NO. 1382

4-30

Signed Plyde Wiley  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

MAY 18 1984