

6030586

00273.00.01

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-01-007

NEUENW SEC. 15, T. 15 S, R. 21 W

4950 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9153

Lease Name PRICE Well # 1 OW20

Operator: VENTURE OIL CO.

County TREGO 133.25

Name & Address 1922 WHITTIER

Well Total Depth 4100 feet

HAYS, KANSAS

Conductor Pipe: Size feet

67601

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor BJ TITAN License Number

Address HAYS KANSAS

Company to plug at: Hour: PM Day: 16 Month: 10 Year: 19 85

Plugging proposal received from TOM ALM

(company name) VENTURA OIL CO. (phone)

were: 8 5/8 SET @ 300' CWC 5 1/2 SET @ 4055 W/185 SX. RECOVERED
5 1/2" CASING ORDER COM. CMT. & SAND ORDER 150 SX. CMT MIX.
4 SX. GEL. BJ TITAN CMT CO. 60/40 PZ 8 5/8 W.P.

Plugging Proposal Received by Carl Goodnow (TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 4: PM Day: 16 Month: 10 Year: 19 85

ACTUAL PLUGGING REPORT BOTTOM - DUMP SAND TO 3500' SPOT W/BAILER 55 SX. COM.

CMT. FULL PIPE. - TOP PLUG. 1ST TRY HOLE IN 8 5/8 BELOW COLLAR. WELD
SPLIT. 2ND TRY BLEW WELD. 3RD TRY CUTOFF 8 5/8 ABOVE CEMENT WELD ON NEW COLLAR.
RIG UP AND RUN BIT ON WT. COLLAR AND TUBING. WASH DOWN SAND AND CLAY
IN HOLE (CAT HAD BACK FILLED INTO CELLAR) TO 650' CIRCULATE CEMENT TO
SURFACE LAY DOWN TUBING. HOOK ON TO 8 5/8 & SQUEEZE 150 SX. CMT MIX.

Remarks: @ 1000' SHUT IN @ 1000' PLUG. COMPLETE
(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED STATE CORPORATION COMMISSION

Signed Carl Goodnow (TECHNICIAN)

DATE OCT 29 1985

OCT 28 1985

INV. NO. 10814

DEC 16 1985 CONSERVATION DIVISION Wichita, Kansas

10-28-1985

FORM CP-2/3 Rev. 01-84