

11-16-87

00.01

To: 6 031003
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 195-20,027 A
1 So NE C
NE SE , SEC. 13, T 15 S, R 21 (W/E)
2086 feet from S section line
766 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135
Operator: John O. Farmer Inc.
Name & Address: Box 352
Russell, Kansas 67665

Lease Name Brenner Well # 1
County Trego 131.95
Well Total Depth 4060' feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Eng License Number 5111

Address Great Bend, Kansas

Company to plug at: Hour: AM Day: 6 Month: Nov Year: 19 87

Plugging proposal received from Jack

(company name) Rockhold (phone)

were: 8 5/8" set at 207' w/165 sks. 5 1/2 set at 4053' w/150 sks PBD 4031'.

Perf 4000' -03'. Order sand and Common Cement. Shoot and pull pipe.

Order 200 sks ATL 65/35 Poz 10% Gel 2% Dical Cement Blend 300# Hulls. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None ✓

Operations Completed: Hour: 11:15 AM Day: 6 Month: Nov Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 8 5/8" w/200 sks Cement Blend w/300# Hulls mixed in.

Max Psi 400# Close in 150#. Plug complete bottom sanded to 3950' w/5 sks Common Cement

on sand. Shots at 3025' and 2542'. Recovered 2542' of 5 1/2" casing.

STATE CORPORATION COMMISSION
12-16-1987
DEC 16 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-6-88

INV. NO. 19367

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow

Form CP-2/3
Rev. 01-84

LR ✓