

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-30140.00.01
NE-SW-NE, Sec. 23, T 14 S, R 21 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name DINWEL Well # 1 (CONWO)

Operator: W.L. HIRKMAN, INC.
Name & Address BOX 195
PRATT, KANS.
67124

County TREGO
Well Total Depth 4012 feet
Conductor Pipe: Size 0 feet 130.39
Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ROCKHOLD ENGINEERING License Number 5111

Address P.O. BOX 698 GREAT BEND, KANS. 67530

Company to plug at: Hour: 10:30 AM Day: 13th Month: DEC. Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO DECON PULLY

(company name) ROCKHOLD ENG. (phone) 316-792-2506

were: 8 5/8" - 238^{EL} SQ. CUL - 1/165^{SK} CNT., 4 1/2" SET @ 3988^{EL} - 1/150^{SK}
PERF'S - 3925^{EL} - 36^{EL}, SHOT 10 TIMES, RECOVERED 1600^{EL} FT.
AT BOTTOM 4^{SK} CNT., SAND 20^{EL} ABOVE PERFS, AND 4^{SK} CNT.
ORDER 165^{SK} 50/100 FORMIX 6% GEL-3% CA-CL, 25^{SK} GEL, 5^{SK} HULL'S TO 8 5/8" PLUG
PUMP IN 8 5/8" SURFACE PIPE WITH PUMP TRUCK.

Signed Marion Schmidt
(TECHNICIAN) 801C

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:30 AM Day: 13th Month: DEC. Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 165^{SK} 50/100 FORMIX 6% GEL-3% CA-CL, 25^{SK} GEL, 5^{SK} HULL'S
AND 8 5/8" PLUG, PUMPED IN WITH PUMP TRUCK.
PUMPED IN 8 5/8" - 4^{SK} HULL'S, 5^{SK} GEL, 25^{SK} CNT, 12^{SK} GEL.
10^{SK} CNT., 8^{SK} GEL, RELEASE PLUG AND TO 5^{SK} CNT.
MAX. PRESSURE 320 PSE CEMENTED BY SUN CNT.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

INVOICED
DATE 1-10-84 DEC 19 1983

Signed Marion Schmidt
(TECHNICIAN) 801C

INV. NO. 8173 W CONSERVATION DIVISION
Wichita, Kansas