

8-8 15.185.01685.0001

To: 120283
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 10/14/52

SE SW SW, SEC. 5, T 21 S, R 13 W/E

330 feet from S section line

4290 feet from E section line

Lease Name Newcombe "A" Well # 2

County Stafford 117.52

Well Total Depth 3616 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 205

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Operator: Petroleum, Inc.
Name & Address 301 North Main, Suite 900
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Petroleum, Inc. License Number 5238

Address 301 North Main, Suite 900, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 8 Month: 8 Year: 19 89

Plugging proposal received from Terry Naylor

(company name) Petroleum, Inc. (phone) 316-793-8471

were: 5 1/2" at 3590' Perfs at 3476-84, 3442-48'

1st plug pump in 5 1/2" casing with 500 lbs. hulls and 180 sx ATL,

2nd plug pump 50 sx ATL down 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 8 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped in 5 1/2" casing with 300 lbs. hulls and 125 sx cement.

Pumping pressure 0-300 psi and shut in 100 psi.

2nd plug pumped in 5 1/2" X 8 5/8" annulus with 200 lbs. hulls and 50 sx cement

Pumping pressure 0-200 psi and shut in 0 (vacuum?).

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1989

Remarks: Used ATL cement by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

8-15-89

INVOICED
(If additional description is necessary, use BACK of this form.)

DATE 8-18-89

Signed Duan Rankin
(TECHNICIAN)

INV. NO. 25677