

To: 060088
STATE CORPORATION COMMISSION
Wichita/State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-185-21,426-0000
S/2 NW SW, SEC. 3, T 21 S, R 13
1650 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 32081

Lease Name Willcut LKC Unit # 5-1

Operator: Smokey Valley Resources, Inc.

County Stafford 114.21

Name & Address 1325 Hwy. 56

Well Total Depth 3514 feet

Lyons, KS 67554

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well X Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 11:45 a.m. Day: 16 Month: 1 Year: 19 98

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Size: 5 1/2" at 3514' w/150 sx cement, PBDT 3460', Perfs at 3408-16, 3438-42, 3446-48'

1st plug sand back to 3200' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 16 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug sanded back to 3200' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

STATE CORPORATION COMMISSION
1-27-1998
JAN 27 1998

CORPORATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1400' of 5 1/2" casing. If additional description is necessary, use BACK of this form.

I (did / ~~XXXXXXX~~) observe this plugging.

Signed Michael Maier (TECHNICIAN)

INVOICED
JAN 28 1998

DATE

INV. NO. 5-0004

1-16