

To: 1 060089
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-185-21,427.0000
SW SW SW, SEC. 3, T 21 S, R 13 W/EX
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 32081

Lease Name Willcut LKC U Well / 5-2
County Stafford 114.08

Operator: Smokey Valley Resources, Inc.
Name:
Address 1325 Hwy. 56
Lyons, KS 67554

Well Total Depth 3510 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SMO Well O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 16 Month: 1 Year: 19 98

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 5 1/2" at 3510' w/150 sx cement, Perfs at 3321-24, 3404-09, 3424-27'

1st plug sand back to 3254' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Mike Maier
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 p.m. Day: 16 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug sanded back to 3254' and dumped 5 sx cement on top of sand
through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(did / observe this plugging.

DATE JAN 28 1998

Signed Michael Maier
(TECHNICIAN)

INV. NO. 50003