

To: 1 060087

1-16

API NUMBER 15- Docket #E-8784

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION App. SW SW NW, SEC. 3, T 21 S, R 13 WXX

130 S. Market, Room 2078
Wichita, KS 67202

2690 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 32081

Lease Name Willcut Well # 4-3

Operator: Smokey Valley Resources, Inc.

County Stafford 114.24

Name & Address 1325 Hwy. 56

Well Total Depth 3515 feet

Lyons, KS 67554

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well Gas Well Input Well X SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 16 Month: 1 Year: 19 98

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 4 1/2" at 3512' w/150 sx cement, PBSD 3483', Perfs at 3404-12'

1st plug sand back to 3300' and dump .4 sx cement on top of sand through bailer,

2nd plug pump 100 sx cement, 100 lbs. hulls mixed in another 100 sx cement.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 a.m. Day: 16 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug sanded back to 3300' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 100 sx cement, then 100 lbs. hulls mixed in with another 100 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

STATE CORPORATION COMMISSION

JAN 27 1998

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 140' of 4 1/2" casing.

If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE JAN 28 1998

Signed Michael Maier (TECHNICIAN)

INV. NO. 5002

1-16