

1 010240

MAY 13 1987

API NUMBER 15-185-22,432.0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW NW, SEC. 3, T 21 S, R 13 W EX

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Fannie Sipes Well # 1-3

Operator: Pintail Petroleum, Ltd.

County Stafford 115.64

Name & Address 412 East Douglas, Suite One

Well Total Depth 3558 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor J.V. Mallard, Inc. License Number 4958

Address Box 1009, McPherson, KS 67460

Company to plug at: Hour: 4:40 p.m. Day: 13 Month: 5 Year: 19 87

Plugging proposal received from Arnie Hess

(company name) J.V. Mallard (phone) 913-731-2869

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 774'
Elevation 1880'

1st plug at 774' with 50 sx cement,

2nd plug at 279' with 40 sx cement,

3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dick Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 13 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 774' with 50 sx cement,

2nd plug at 279' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 5-18-87

INV. NO. 16944

5-13

5-15-1987

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1987

Signed [Signature]
CONSERVATION DIVISION
WICHITA, KANSAS
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 04 30 87 month day year

API Number 15- 185-22, 432-0000

OPERATOR: License # 5086 Name Pintail Petroleum, Ltd. Address 412 E. Douglas, Suite One City/State/Zip Wichita, KS 67202 Contact Person Flip Phillips Phone 316/263-2243

NE NW NW Sec. 3 Twp 21 S, Rg. 13 X West 4950 Ft. from South Line of Section 4290 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County Stafford

CONTRACTOR: License # 4958 Name J V Mallard, Inc. City/State McPherson, KS 67460

Lease Name Fannie Sipes Well # 1-3 Ground surface elevation 1880 feet MSL

Well Drilled For: X Oil Storage Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Domestic well within 330 feet yes Xno Municipal well within one mile: yes Xno

Depth to bottom of fresh water 90 feet Depth to bottom of usable water 250 feet

If OWWO: old well info as follows:

Surface pipe by Alternate: 1 X 2 1/2 Surface pipe planned to be set 250 feet

Operator Well Name Comp Date Old Total Depth

Conductor pipe required Projected Total Depth 3600 feet

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications.

Date Signature of Operator or Agent Flip Phillips Title Agent

For KCC Use:

Conductor Pipe Required 250 feet; Minimum Surface Pipe Required 250 feet per Alt. 0 4

This Authorization Expires 10-29-87 Approved By 4-29-87

SPUD 5-5-87 250'-8 3/8"

NE NW NW Sec. 3 Twp. 21 S, Rg. 13 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Arbuckle, if penetrated

1st plug @ ft. deep. more than 50' or formation with 100' 100 SX feet of 60/40 pozmix, 6% gel
2nd plug @ ft. deep. Anhydrite 75' or formation with 200' 50 SX feet of same
3rd plug @ ft. deep. B/Cheyenne or formation with 300' feet of same
4th plug @ ft. deep. Surf-30 below surf pipe or formation with 400' 40 SX feet of same
5th plug @ ft. deep. no solid bridge or formation with 40' 10 SX feet of same
(2) Rathole to surface minus 5 feet circ cement from 40-30 to surf. Dick gauge order

Table with columns: PUSHER, TD, SURFACE PIPE @, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ FT. W/ SX, 2nd PLUG @ FT. W/ SX, 3rd PLUG @ FT. W/ SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY, TECHNICIAN

316-792-8261 tone 03304020

RECEIVED STATE CORPORATION COMMISSION CONSERVATION DIVISION Wichita, Kansas