

1080375

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,214 .0000

W/2 NE SW, SEC. 23, T 21 S, R 12 W/E

1980 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9800

Lease Name Widener East Well # 1

Operator: Double R Oil Company

County Stafford 120.90

Name & Address P. O. Box 506

Well Total Depth 3720 (Arbuckle) feet

McCook, NB 69001

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mohawk Drilling, Inc. License Number 6394

Address 614 Patton Road, Box 1362, Great Bend, KS 67530

Company to plug at: Hour: 11:00 pm Day: 8 Month: May Year: 19 85

Plugging proposal received from Mr. Hilbern

(company name) Mohawk (phone) 316-792-4531

Elevation 1843'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 632.48'

1st plug at 3610' with 40 sx cement

2nd plug at 658' with 50 sx cement

3rd plug at 300' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement  
Plugging Proposal Received by J. H. [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:15 am Day: 9 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3610' with 40 sx cement, 2nd plug at 658' with 50 sx

cement, 3rd plug at 300' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

5-21-1985

MAY 21 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by BJ-Titan

(If additional description is necessary, use BACK of this form.)

(XXXX did not) observe this plugging.

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 5-21-85

Signed J. H. [Signature] (TECHNICIAN)

INV. NO. 8205

JUN 6 1985

15-185-22214-0000

CARD MUST BE TYPED

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

Starting Date: Set 260 4-29-85  
month day year

API Number 15- 185-22,214 5-9-85  
BS. Titman

OPERATOR: License # 2800

W/2 NE SW... Sec 23. Twp 21. S. Rge 12.  En-  We

Name Double R Oil Company

...1980... Ft North from Southeast Corner of Section

Address P.O. Box 506

...3630... Ft West from Southeast Corner of Section

City/State/Zip McCook, Nebraska 69001

(Note: Locate well on Section Plat on reverse side)

Contact Person Bob Arends

Phone 308-278-2061

CONTRACTOR: License # 6394

Name Mohawk Drilling, Inc.

City/State Great Bend, Kansas

Well Drilled For: Well Class: Type Equipment:

- Oil  Swd  Infield  Mud Rotary
- Gas  Inj  Pool Ext.  Air Rotary
- OWWO  Expl  Wildcat  Cable

If OWWO: old well info as follows:

Operator .....

Well Name .....

Comp Date ..... Old Total Depth .....

Projected Total Depth 3700' feet

Projected Formation at TD Arbuckle

Expected Producing Formations Arbuckle - Kansas City

Nearest lease or unit boundary line 330 West feet

County Stafford

Lease Name Widener East Well# 1

Domestic well within 330 feet:  yes  no

Municipal well within one mile:  yes  no

Depth to Bottom of fresh water 160-220 <sup>MHC</sup> feet

Lowest usable water formation Dakota

Depth to Bottom of usable water Unknown <sup>MHC</sup> 240 feet

Surface pipe by Alternate:  1  2  MHC

Surface pipe to be set 260 feet

Conductor pipe if any required None feet

Ground surface elevation 1843 feet MSL

This Authorization Expires 10-16-85

Approved By 4-16-85 R.

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 4-15-85 Signature of Operator or Agent

Joe E. Blougher  
Water User

Mohawk Drilling, Inc  
President

Form C-1 4/84

MHC / UOHE 4-16-85

RECEIVED  
STATE CORPORATION COMMISSION

MAY 21 1985

CONSERVATION DIVISION  
Wichita, Kansas