

To: 1 120738 9-29
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,875-0000 2701
NE NE NE, SEC. 23, T. 21 S, R 12 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name & Address RR 1, Box 183 B
Great Bend, KS 67530

4950 feet from S section line
330 feet from E section line
Lease Name Monte Well # 1
County Stafford 117-81
Well Total Depth 3625 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 313

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 29 Month: 9 Year: 1992
Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 610-37'

- 1st plug at 640' with 50 sx cement,
- 2nd plug at 340' with 50 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:15 p.m. Day: 29 Month: 9 Year: 1992

- ACTUAL PLUGGING REPORT 1st plug at 640' with 50 sx cement,
2nd plug at 340' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1992
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
I (did ~~not~~) observe this plugging.
DATE 10-21-92
INV. NO. 36536

Signed Glenn Barlow
(TECHNICIAN) RWZ

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 9-23-92

State of Kansas 15-185-22,875-00-00
NOTICE OF INTENTION TO DRILL

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

DISTRICT # 1
35A? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date .. September .. 22 .. 1992 ..
month day year

Spot NE NE NE Sec 23 Twp 21 S Rg 12 East West

OPERATOR: License # 6039
Name: L. D. Drilling, Inc.
Address: R.R. 1 Box 183 B
City/State/Zip: Great Bend, Kansas 67530
Contact Person: L. D. Davis
Phone: (216) 793-3051

4950 feet from South / North line of Section
330 feet from East / West line of Section
15 SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Stafford
Lease Name: MONTE Well #: 1
Field Name: STEVE

CONTRACTOR: License #: 6039
Name: L. D. Drilling, Inc.

* Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Arbuckle

Well Drilled For: Well Class: Type Equipment:
..X Oil ... Enh Rec X Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OUMD ... Disposal ... Wildcat ... Cable
... Seismic: ... # of Holes ... Other

Nearest lease or unit boundary: 330
Ground Surface Elevation: 1831 feet MSL
Water well within one-quarter mile: X yes no
Public water supply well within one mile: X yes no

If OUMD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Depth to bottom of fresh water: 180
Depth to bottom of usable water: 230
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 300
Length of Conductor pipe required: none

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Projected Total Depth: 3600
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
X well X fare pond other

OWR Permit #: applied for
Will Cores be Taken? yes X no
If yes, proposed zone: 200' Alt. I Req.

* Prorated for Penn, cgl. Exp. 3/18/93

AFFIDAVIT

Pusher Greg SPUD DATE 9-23-92 INIT. DR
 LENGTH SURFACE PLANNED 300'
 RESERVE PIT STATUS- REMOVE FLUID LINED
 after salt sect. bbls. when done bbls.
 RATHOLED AHEAD? Y N SIZE HOLE
 SURFACE PIPE 8 3/8 @ 3/3 CONDUCTOR
 ANHYDRITE T- 610 B- 637 ELEVATION
 TD 463625 FORMATION
 RAN PIPE @ DV TOOL ALT II DONE
 @ SX TOP of Arb 3572 SX Y N
 Arbuckle Plug @ 44 Ft. W/ 50 SX
 Hug./Council @ Ft. W/ SX
637 Anhydrite Base @ 640 Ft. W/ 50 SX
 1/2 Base Anyh. @ Ft. W/ SX
 1/2, 1/2 Plug @ Ft. W/ SX
 2 1/2 Bottom Surface @ 340 Ft. W/ 50 SX
 40' Plug @ 40 Ft. W/ 10 SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 15 SX
 WATER WELL SX (Irr. Well Pond Hauling)
 TECHNICIAN CK DATE 9-28-92
 TYPE OF CEMENT CT
 STARTING TIME 1:30 (AM/PM) DATE 9-
 COMPLETION TIME 2:15 (AM/PM) DATE
 CEMENT COMPANY ALLI-W
 Note: DR to witness