

7-7

1 031014

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,782.0000

SE SW NE, SEC. 6, T 21 S, R 13 W/E

2970 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5990

Lease Name Morrison Trust Well # 1

Operator: Paul L. Bandy
Name & Address: P.O. Box 364
Canton, KS 67428

County Stafford 116.87

Well Total Depth 3596 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 7 Month: 7 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" 3602' PBTD 3597' Perfs at 3594-3596' Elevation 1905' GL

1st plug sand back to 3540' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:15 p.m. Day: 7 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3540' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 100 psi and shut in 0 psi.

RECEIVED STATE CORPORATION COMMISSION

SEP 11 1989 7-11-1989 CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED ~~RECEIVED~~ did not observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 7-13-89

INV. NO. 25320 7-7

SEP 11 1989