

7-7 15.185.21353.0000

1 031015

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-20,436

NE NW SE, SEC. 6, T 21 S, R 13 W/E

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5990

Lease Name Morrison Trust Well # 2

Operator: Paul L. Bandy

County Stafford 119.08

Name & Address P.O. Box 364

Well Total Depth 3664 feet

Canton, KS 67428

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 7 Month: 7 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 3232' PBSD 3167' Perfs at 3124-32, 3019-26, 3000-07, 2976-82, 2968-72'
1st plug sand back to 2918' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2 p.m. Day: 7 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 2918' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 100 psi and shut in 0 psi.

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2170' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 7-13-89

INV. NO. 25321

7-7 SEP 11 1989