

1052372

TO: STATE CORPORATION COMMISSION API NUMBER 15-185-23,049.0001 APP. W/2 SW NW SEC. 6, T 21 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 1925 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 120 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MORRISON UNIT WELL # 1

TECHNICIAN'S PLUGGING REPORT 2/24 COUNTY STAFFORD 116.94

OPERATOR LICENSE # 5338 WELL TOTAL DEPTH 3598 FEET

OPERATOR: TOM KAT LTD. PRODUCTION CSG: SIZE 5 1/2" @ 3593' WITH 100 SX

NAME AND ADDRESS PO BOX 780581 SURFACE CASING: SIZE 8 5/8" @ 264' WITH SX

ADDRESS WICHITA, KS 67278-0581

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 24 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: OPEN HOLE AT 3593-98 DV @ 829' WITH 100 SX CEMENT.

PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 1 SX OF CEMENT. MAXIMUM PRESSURE AT 500 PSI. SHUT

IN WITH 500 PSI. PUMPED DOWN 5 1/2" CASING WITH 200# HULLS - 35 SX CEMENT - 9 SX GEL -

160 SX CEMENT. MAXIMUM PRESSURE AT 2750 PSIG. SHUT IN PRESSURE AT 1750 PSIG.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:18 PM DAY: 24 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 1 SX OF CEMENT. MAXIMUM PRESSURE 500 PSI. SHUT IN

500 PSI. PUMPED DOWN 5 1/2" CASING WITH 200# HULLS - 35 SX CEMENT - 9 SX GEL - 160 SX CEMENT

MAXIMUM PRESSURE 2750 PSIG. SHUT IN PRESSURE 1750 PSIG.

RECEIVED STATE CORPORATION COMMISSION

FEB 28 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS CONSERVATION DIVISION Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING

INVOICED SIGNED

Richard W. Lacey (TECHNICIAN)

FORM CP-2/3

DATE 2/28/00

INV. NO. 0606316

Handwritten signature and initials