

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23043-00-00
Spot: E2NWNWSE Sec/Twnshp/Rge: 34-16S-12W
2460 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: JENISCH B Well Number: 1
County: BARTON Total Vertical Depth: 3330 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 332 w/200 sxs cmt
Production: Size 5.5 feet: 3324
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/02/2002 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: DUANCE ACHTERBERG Company: FLATLAND MAINTENANCE SERVI Phone: (785) 635-7335

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/02/2002 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 250' - 740' - 1700'.
TIH with tubing to 1800'.
Mixed and pumped 130 sxs with 500# hulls.
Pulled up to 900' and circulated cement up 5 1/2" with 65 sxs.
Swaged onto 5 1/2" and circulated cement up 8 5/8" with 40 sxs.

RECEIVED

MAY 10 2002

KCC WICHITA

5-10-2002

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

MAY 08 2002

ASSOCIATES OIL & GAS, INC.

555 N. WOODLAWN, #114
WICHITA, KANSAS 67208

#1 "B" JENISCH

34-16-12W
150'E,

CONTR HUSKY DRILLING CO., INC. CTY BARTON


C NW NW SE

GEOLOGICAL FIELD BEAVER SO.

ELV 1877 KB SPD 2/17/83 CARD ISSUED 3/31/83 IP P 84 BOPD, NW

API 15-009-23.043

ARB OH 3324-3330



LOG	Tops	Depth/Datum	
TOP	2672	795	8 5/8 " 332/200SX; 5 1/2 " 3324
HEEB	2954	1077	DST (1) 3050-70 (BR LM, LANS) / 30-60-30-60, REC 30' O SPTD M, (LESS THAN 1% O), 60' M, SIP 837-815#, FP 34-45 / 55-56#
TOR	2967	1090	DST (2) 3136-48 (LANS) / 30-60-30-60, REC 30' SO & WGM (1% O, 30% W, 69% M), 120' MCW, SIP 792-770#, FP 34-45 / 55-79#
BR LM	3042	1165	
LANS	3061	1184	
BKC	3301	1424	DST (3) 3309-22 (CONG, ARB) / 30-60-30-60, REC 10' SOCM, 6' FROTHY O ON TOP TOOL, SIP 894-837#, FP 34-34 / 34-34#
CONG	3304	1427	
ARB	3318	1441	DST (4) 3309-30 (CONG, ARB) / 30-60-30-60, REC 2850' O - NW, SIP 1118-1118#, FP 680-961 / 1062-1073#
RTD	3330	1453	MIC - CO, (ARB OH), SWB 15 BFPH - NW, NAT, 1000' FROM SURFACE, 6 PULLS PER HR, 100' PER PULL / 2 HRS, ONFU 3150' O, R&T, POP, P 170 BO / OVERNIGHT, P & FLO 84 BOPD - NW, 3/24/83

NOTE: 3/31/83 - ORIGINALLY FIRST REPORTED IN 330'FNL&480'FWL, SE/4

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS