

4 060221

7-18

246
P

API NUMBER 15- 009-23,161-00-00

NE SE SW, SEC. 34, T 16 S, R 12 W EX

990 feet from S section line

2970 feet from E section line

Lease Name Beran Well # 1-A

County Barton 110.50

Well Total Depth 3400 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 328

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6425

Operator: Amber Oil Company
Name & Address Suite 360, Three Corp. Plaza
Oklahoma City, OK 73112

Abandoned Oil Well XXXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Great Bend, KS

Company to plug at: Hour: 8:30AM Day: 18 Month: July Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone)

Order 200 sxs. 60/40pos 8%gel.

Sand back bottom to 50' above perms and spot 5 sxs. cement with bailer.

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1991

Plugging Proposal Received by Gib Scheck (TECHNICIAN)
Conservation Division
Wichita, Kansas

Plugging Operations attended by Agent?: All XXXXXX Part None

Operations Completed: Hour: 9:30AM Day: 18 Month: July Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" to 328' Shot off and recovered 1605' of 5 1/2".

Pulled casing to 790' and spotted 50 sxs. cement and displaced to 700'.

Pulled casing to 370' and circulated cement to surface with 125 sxs. cement.

Pulled casing and topped well with 15 sxs. cement.

Remarks: B-J Services Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-12-91

INV. NO. 32661

Gib S.

Signed Herb Deines (TECHNICIAN)

Herb Deines