

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23190-00-00

Spot: CSWNWSE

Sec/Twnshp/Rge: 34-16S-12W

1650 feet from S Section Line, 2310 feet from E Section Line

Lease/Unit Name: JENISCH B

Well Number: 3

County: BARTON

Total Vertical Depth: 3379 feet

Operator License No.: 101

Conductor Pipe: Size

feet:

Op Name: KCC FEE FUND

Surface Casing: Size 8.625

feet: 361

w/185 sxs cmt

Address: 130 S. MARKET, ROOM 2078

Production: Size 5.5

feet: 3371

WICHITA, KS 67202

Liner: Size

feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/02/2002 1:00 PM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE INC

Proposal Rcvd. from: DUANE ACHTERBERG

Company: FLATLAND MAINTENANCE SERVI Phone: (785) 635-7335

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/02/2002 4:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 250' - 720' - 1700'.

TIH with tubing to 1800' - tied onto and circulated cement up 5 1/2" with 150 sxs cement and 500# hulls.

POOH.

Swaged onto 5 1/2" and circulated cement up 8 5/8" with 60 sxs.

Shut in and pumped to pressure with 90 sxs cement.

Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED

MAY 10 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

MAY 08 2002

ASSOCIATES OIL & GAS, INC.

555 N. WOODLAWN, #114

WICHITA, KS 67208

#3 "B" JENISCH

34-16-12W
SW NW SE

CONTR COUGAR DRILLING

CTY BARTON

GEOL

FIELD BEAVER SO.

ELY 1873 KB SPD 7/12/83

CARD ISSUED 9/1/83

IP P 65 BOPD, NW

API 15-009-23,190

ARB 3330-3336

LOG	Tops	Depth	Datum
HEEB	2955	1082	
TOR	2970	1097	
DOUG	2982	1109	
BR LM	3045	1172	
LANS	3063	1190	
BKC	3303	1430	
CONG	3311	1438	
ARB	3322	1449	
RTD	3379	1506	

8 5/8 " 361/1855X; 5 1/2 " 3371

DST (1) 3119-47 (LKC) / 30-60-30-60, REC 1647' SGCSW, SIP 972-961#, FP 179-567 / 635-770#

DST (2) 3307-30 (CONG, ARB) / 30-60-30-60, REC 3045' CGO, SIP 1107-1107#, FP 181-420 / 477-546#

DST (3) 3336-44 (ARB) / 30-60-30-60, REC 3045' CGO, SIP 1107-1107#, FP 227-792 / 814-1040#

DST (4) 3349-54 (ARB) / 30-60-30-60, REC 120' CGO, 480' OCW (10% OIL), 140' SOCW (10% OIL), 660' W, SIP 1118-1118#, FP 91-285 / 447-666#

MIC - CO, PF (ARB) 3330-36, SWB DWN & REC 14 BOPH, 100' OB, NAT, T&R, POP, P 65 BOPD, NW, 8/15/83

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS